CHITALDRUG DISTRICT.

Abstract Notification, dated 6th June 1933.

The attention of the public is invited to pages 711 and 712, Part VI of the *Mysore Gazette*, dated 15th June 1933 regarding the auction sale of the right of collecting Tupra leaves in Chitaldrug Taluk during the years 1933-35 fixed for 3rd July 1933.

B. N. IYENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Abstract Notice.

The attention of the public is invited to the notification inviting tenders for the restoration of Tharabahalli-Attikere breached tank Reg. No. 112 of Hoskote Taluk, published on pages 712 and 713 of Part VI of the *Mysore Gazette*, dated 15th June 1933.

2. The last date of receipt of tender is 3rd July 1933, 2 P.M. and earnest money to be deposited is Rs. 300.

H. F. MARKER,
Executive Engineer.

KOLAR DIVISION.

Abstract Noticcation, dated 29th May 1933.

The attention of the public is invited to the notification published in pages 682 and 683 of Part VI of the *Mysore Gazette*, dated 8th June 1933, calling for tenders for the work of Restoring Kusandra-Balayankunte Regd. No. 253, Serial No. 200 of Srinivaspur Taluk.

The last date fixed for receipt of tender is 4th July 1933 up to 2 P.M.

Abstract Notification, dated 29th May 1933.

The attention of the public is invited to the notification, published in pages 681 and 682, Part VI of the *Mysore Gazette*, dated 8th June 1933, calling for tenders for the work of Restoring Lakshmicagara-Kodagikere, Regd. No. 203—647 of Malur Taluk.

The last date fixed for receipt of tender is 3rd July 1933 up to 2 P.M.

C. T. NARASIMHA IYENGAR,
Executive Engineer.

MYSORE DIVISION.

Notification, dated 13th June 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 12 noon, on 10th July 1933, for restoring the Seegavalu Minor Tank, Yedatore Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes as earnest money and be superscribed "Tender for Restoring Seegavalu Minor Tank, Yedatore Taluk", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of disputes about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotations quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract Estimate for Restoring the Seegavalu Minor Tank, Yedatore Taluk.

No.	Items of work	Unit	Quantity
	Bund.		
1	Earthwork to bund including watering and consolidation	C.yd.	8981
2	Carving and fixing old gradestones	Each	10
3	Supplying and fixing new grade stones	,,	22
4	Register number stone	,,	1
5	Removing toddy trees with roots (big trees) ...	,,	26
6	Do do (small trees) ..	,,	20
7	Cutting grips in the bund for putting new bank and jungle clearing, etc.	Grade	30
8	Supplying and fixing rough top width stones	Each	32
	Sluice.		
1.	Supplying and fixing new iron rod and plug with locking arrangements.	Lump sum	
2	Repairing cistern and tunnel	Lump sum	
	Waste Weir.		
1	Removing the flank bund and using the same on bund ..	C.yd.	133
2	Excavating foundations	,,	71
3	Concrete in surki mortar	C.ft.	535
4	Burnt brick in surki mortar	,,	1537
5	Burnt stone slabs dressed and fixed of 6" thick ...	S.ft.	236
6	Plastering with surki mortar	Sqr.	2·42
7	Filling in jelly for scours	C.yd.	250
8	New rough stone work (suji cut apron)	,,	282
9	Provision for clearing site at scours, etc., bailing water and unforeseen works such as building cody wall for the recently damaged portion.	Lump sum	

K. NARAYANA IYENGAR,
Executive Engineer.

OFFICE OF THE EXECUTIVE ENGINEER, No. IV TUNNEL DIVISION, HULIKERE.

Notification, dated 9th June 1933.

It is hereby notified for the information of the public that the unserviceable tools and plant and surgical instruments and released timber noted below will be sold by public auction from 8 A.M. on the 24th July 1933 and subsequent days, if necessary, at Hulikere stores premises and Kodiyala Sub-Division Office :—